

Bid Addendum Report

Sundarharaicha Municipality

Sundarharaicha Municipality
Morang
Koshi Haraicha, Morang
Province One
Biratchowk, Sundarharaicha Municipality
Nepal

Addendum No: 1

Published On: 19-05-2023 14:00

Invitation No: SHM/MOR/NCB/W-19/2079/080

Dated On: 09-05-2023 00:00



[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
20182175
सुन्दरहरैचा नगरपालिका
मोरङ, कोशी प्रदेश, नेपाल


Procurement Item Details

SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)
1	Provide and instalation of project information Board 1.0 x1.50m in iron posts including cost of excavation, M10 concrete for foundation, backfill and all other incidental work so as to complete the work as specified & Site Clearance works	PS	1	3500	3500
2	Lab Testing of materials and works as per requirement and instructed by Engineer	Ps	1	40000	40000
3	Insurance of works, equipment, workforces, employees and Third party Insurance against damage to other persons and property.	Ps	1	40000	40000

2 Construction work

Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Foundation excavation in soft soil and silty soil, lifting up to 1.5 meter and disposal with haulage distance 10m (Mechanical Means)	Cum	68.0			
2	Earth Back Filling in foundation trenches & Floor in 15 c.m. layers with Transported Soil, water sprinkling & manual compaction as per speciication and instruction all complete.	Cum	30.68			
3	Stone Soling in foundation trench, finishing to approved level, line and dimensions as per instruction & specification all complete work.	Cum	14.93			
4	Chimney Bhatta (Terai) Brickwork in cement sand mortar in 1:6 In ground Floor with 1 st class bricks in perfect line and level including wetting the bricks, packing the joints and curing the work in all types and thickness of walls, column etc. as per instruction & specification complete work	Cum	63.7			
5	Plain Cement Concrete (1:3:6.) M10 in foundation & wall with cement, sand and aggregate including mixing, laying, finishing to approved level, line and dimensions and curing as per instruction & specification complete work.	Cum	13.6			
6	P.C.C. M15 (1:2:4) in foundation, walls, beams, slabs, sill, stitches, lintels etc.with cement sand and graded coarse aggregate (Crushed) including mixing concrete, lead upto 30m, laying, compacting the concrete mix with vibrator machine, finishing to approved level lines and dimensions and curing as per instruction & specification complete work.	Cum	5.99			




9.1.

9.1.

9.1.

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
7	P.C.C. M20 (1:1.5:3) for R.C.C. Work in Super structure, columns, beams, decks, slabs, etc.with cement sand and graded coarse aggregate (river bed foruwa) including mixing with concrete, lead upto 30m, compacting the concrete mix with vibrator machine.laying, finishing to approved level lines and dimensions and curing as per instruction & specification complete work.	Cum	123.4			
8	TMT Reinforcement bar (Fe 500) for RCC Works, tested including straightening, cleaning, cutting, bending and fixing in position with 20 B.G. annealed binding wire as per drawing, specifications and instructions by site-engineer all complete work.	Kg	12081.08			
9	M.S Grill Work with MS Square Grill in MS Angle 25x25x3 mm Frame with 10mm Square bar for Vertical @ 4"c/c & 6 Horizontal 10mm Square bar (minimum weight 14kg/sqm) Grill as per Specification and as directed by Site Engineer. and manufacturer including 2 coats of aluminium paints over one coat of primer and fixing in position as per instructions & specifications all complete work.	Kg	1014.59			
10	Steel Railing for Staircase/Verandah (S.S.Pipe) Fabrication & installation (50mm dia. Hand rail, 40mm dia. Vertical post, 20mm dia. Bracing 3 lines) 90 cm height good finishing including fixing as per specification and instruction complete work	Rm	5.79			
11	MS Collapsible Gates (minimum weight 50 kg/sqm) Grill as per Specification and as directed by Site Engineer. and manufacturer including 2 coats of aluminium paints over one coat of primer and fixing in position as per instructions & specifications all complete work.	Kg	292.67			



प्रमुख प्रशासकीय अधिकारी

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
12	Formwork/ Centering & Shuttering with 18mm thick Plywood for all type of concrete works necessary propping, scaffolding, staging, supporting inclusive wedging and cutting holes for utilization work till the support is fully unyielding as per instructions & specifications complete work .	Sqm	783.37			
13	Supply, preparation & fixing of seasoned (100x75)mm Hard Saal wood frame (chauhkat) for Door, (75x60)mm Saal wood Frame window & ventilation with necessary hold fast, screws etc. as per specifications & instructions of site engineer.	Cum	0.63			
14	Supply, preparation & fixing of Flush Door Shutter of seasoned Saal Hard wood of 38mm thick frame and salwood shutter with necessary hinges,tower bolts, locking sets, screws, nails ,nut bolts all complete as per specifications & instructions by site engineer.	Sqm	23.92			
15	Supply, preparation & fixing of seasoned SAAL Hard wood (38*75) mm frame & 4 mm glass with wooden beat fully glazed window shutter with necessary hinges,tower bolts, screws, nails all complete as per specifications & instructions of site engineer.	Sqm	3.02			
16	Aluminium Framed Sliding Window with Flymesh Shutter in the Section of 78x30x1.1mm including 5mm thick glass Fixing as per specification and direction complete work.	Sqm	67.64			
17	Aluminium Framed Fixed Partition with 5mm glass and 9mm laminated board in the section 101 x 45 x 1.2 mm	Sqm	3.81			
18	12.5 mm thick cement sand plaster(1:4) on Masonry walls (inside) of good finish including racking the joints, wetting the surface & curing the work as per specifications & direction all complete.	Sqm	1246.47			
19	3mm thick (1:1) Cement sand punning work on Floor etc including mixing, laying, finishing to approved level, line and dimensions and curing as per instruction & specification all complete work.	Sqm	55.31			
20	Two coat ready made weather coat paint with one coat primer application in new plastered surface	Sqm	313.16			



०५/०२/०८
प्रमुख प्रशासकीय अधिकारी

Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
21	Two coat ready made interior emulsion paint with one coat primer application in new plastered surface	Sqm	947.11			
22	Porcelain glazed tiles flooring in (1:4) cement / sand mortar for floor laid in proper slope	Sqm	175.59			
23	Providing Porcelain Glazed (white/Digital coloured) Wall Tiles white/ coloured in floor with cement sand mortar 1:4 with white cement slurry including polishing to smooth finished glazed surface as per instruction & specification all complete work.	Sqm	22.35			
	Anti slip Dotted Cement Tile on floor consisting of 20mm th. Cement sand 1:2 including finished surface all complete as per specification and instruction all complete work.	Sqm	29.73			
25	16 mm thick Rajasthani marble/ Granite marble laying in 20 mm thick (1:2) cement / sand mortar including polishing	Sqm	10.31			
26	Dismantling of existing structure like Building structure comprising of masonry, cement concrete, wood works, steel work, including scaffolding wherever necessary, sorting the dismantled Material, disposal of unserviceable Material and stacking the serviceable Material with all lifts and lead of 1000 meters, dismantled Material.	Sqm	181.18			
27	Dismantling of existing structure like Building structure comprising of masonry, cement concrete, wood works, steel work & stacking the serviceable Material with all lifts and lead of 1000 meters, dismantled Material.	Cum	56.36			
28	Electrical Wiring PVC pipe in both Slab With Pannel, junction ,DB etc (70 points) & Ground & First floor wiring 18 nos fan, 36nos led bulb,for power sucket 2.5 mm multistand wire,for bulb & fan 1.5mm multistand wire and mai DB Box 2 nos , earthing as per nomes with instillation wiring all complete.	Ls	1.0			
29	Sanitary Work (for Toilet Simple indian pan 4 nos, 3washbasin with Tap,6 water tap ,1000Ltr.Hill tank (NS) eqv. & accessories& fitting pipe , gate ball ,32 mm ,25mm pvc ipe for all toilet & basin from water Tank supply all Complete	Ls	1.0			



२०७३.०५
प्रमुख प्रशासकीय अधिकारी



Chapter: Special Conditions of Contract (SCC)

Sl. No.	Relevant Clause No / Name	Existing Clause	Modified Clause
1	GCC 1.1 (bb)	Er. Sunil Adhikari	Ambika Prasad Chaulagain

Chapter: Price Adjustment

New Values	Base Price of Construction Materials applicable for price adjustment shall be as per the Table of Adjustment Data submitted by Bidder together with the Letter of Bid which is approved by the Project manager and attached as Annex-1				
	Sl. No.	Construction Material	Unit	Base Price (NRs/Unit) (Ex-	Source (Factory)
	1	0	0	0	0

अ.प्र.

अ.प्र.

अ.प्र.
2078/2/02
अ.प्र. प्रसाद चौलागाई
प्रमुख प्रशासकीय अधिकारी

Abbreviations

BD	Bidding Document
BDF	Bidding Forms
BDS	Bid Data Sheet
BOQ	Bill of Quantities
COF	Contract Forms
DP	Development Partners
DoLI	Department of Local Infrastructure
ELI	Eligibility
EQC	Evaluation and Qualification Criteria
EXP	Experience
FIN	Financial
GCC	General Conditions of Contract
GoN ¹	Government of Nepal
ICC	International Chamber of Commerce
IFB	Invitation for Bids
ITB	Instructions to Bidders
JV	Joint Venture
LIT	Litigation
NCB	National Competitive Bidding
PAN	Permanent Account Number
PPA	Public Procurement Act
PPMO	Public Procurement Monitoring Office
PPR	Public Procurement Regulations
PL	Profit & Loss
SBD	Standard Bidding Document
SCC	Special Conditions of Contract
TS	Technical Specifications
VAT	Value Added Tax

¹ "GoN" word indicates all public entities according to Public Procurement Act, 2063



[Handwritten signature]

[Handwritten signature]

[Handwritten signature]
 २०७३
 प्रमुख प्रशासकीय अधिकारी

WRQ Works Requirements



अ.प्र.

[Handwritten signature]
२०७०/०२/०५
प्रमुख प्रशासकीय अधिकारी